

**N40085-08-B-0431**  
**WO# 4126905**  
**M1 Project # 8M026CN**  
**G-526 Front Parking Lot Overlay**  
**Prepared By: Matthew O'Leary**

**Scope of Work**

**General Description:** The contractor shall provide all material, labor, equipment and supervision required to accomplish the following. Provide a 2" wearing course of Superpave asphalt, paint parking stalls for parking lot in front of G526 Camp Geiger (see site plan) . The measurements furnished here are for reference only. This scope of work is to be accomplished at building G526 front Parking Lot Camp Geiger.

**Detailed Requirements and Specifications:** Remove any sand, rocks, loose asphalt, dirt, and organic material and expose the edges of the asphalt to be overlaid. Clean the designated overlay areas (by sweeping or some other means) and prep for new asphalt. Apply a tack coat at the manufacturer's specifications on the existing asphalt to be overlaid. Provide a 2 inch wearing course of S-9.5B Superpave asphalt (NCDOT compliant) compacted to 91% on the overlay area. The total area to be overlaid is approximately 4610 SY. All paved areas shall be graded to allow a minimum 2% slope away from the buildings and towards existing drainage. Provide a smooth and seamless transition from existing Parking Lot and curbs to the newly paved Parking Lot.  
See Site Plan for the Pavement Overlay Detail.

Paint Parking Stalls to reflect existing layout. The Parking Stall lines will be painted white and be 4" in width. Paint will be acrylic latex marking paint applied at the manufacturers recommended thickness.

**Special Requirements:** The building will remain in operation during the entire construction period. The contractor shall conduct their operations so as to cause the least possible interference with normal operations of the activity. The Point of Contact at the work site for this project is Msgt Childs 449-0065. Make arrangements with the POC one week prior to the project start date so vehicles can be moved and work can commence.