

CONTRACT # N40085-08-B-0470
PROJECT # 8R905CN
MAXIMO# 4143189

TITLE: AS-4158 PARKING LOT EXTENSION

ATTACHMENTS:

1. **Site Plan**
- 2.

SCOPE OF WORK

General Description: The contractor shall provide all material, labor, equipment and supervision required to accomplish the following. Extend parking lot at AS-4158 by providing a 2" wearing course of Superpave asphalt to an area of approximately 4585 SYDS. The measurements furnished here are for reference only. This scope of work is to be accomplished at building AS-4158, New River Air Station.

Detailed Requirements and Specifications:

The Contractor Shall:

1. Add up to 500 tons of ABC rock in area to be paved. (*SEE SITE PLAN*)
2. Grade additional ABC rock on existing gravel parking lot to be compacted to 8" depth in area shown on site plan.
3. Provide a 2" wearing course of S-9.5B Superpave asphalt (NC DOT Compliant) compacted to 91% in area shown on site plan.
4. Ensure paved areas are graded to allow a minimum 2% slope away from surrounding buildings and towards existing drainage.
5. Provide a smooth and seamless transition from existing asphalt parking lot to the newly paved parking lot.
6. Ensure all disturbed areas are backfilled with topsoil, raked and seeded with Coastal Lawn Mix at a rate of 5 pounds per 1,000 square feet.
7. Clean up and haul off all debris and soil/rock materials.

Special Requirements: The building will remain in operation during the entire construction period. The contractor shall conduct their operations so as to cause the least possible interference with normal operations of the activity. The Point of Contact at the work site for this project is CWO Clark 449-6785. Make arrangements with the POC one week prior to the project start date so vehicles can be moved and work can commence.