

**CONTRACT # N40085-09-B-0411**  
**PROJECT # 9M015CN**  
**MAXIMO# 4194166**

**TITLE: ALZ2 HELO PAD OVERLAY**

**ATTACHMENTS:**

**1. Site Plan**

**SCOPE OF WORK**

**General Description:** The contractor shall provide all material, labor, equipment and supervision required to accomplish the following. Provide a 2" asphalt overlay on the helicopter landing pad near Bldg. H-1. (Approx 400 Sq. Yds.). The measurements furnished here are for reference only.

**Detailed Requirements and Specifications:**

**The Contractor Shall:**

- Spray area to be paved with weed killer where vegetation exists allowing 10 days for results.
- Remove any sand, rocks, loose asphalt, dirt, and organic material and expose the edges of the asphalt to be overlaid.
- Clean the designated overlay area (by sweeping or some other means) and prep for new asphalt.
- Apply a tack coat at the manufacturer's specifications on the existing asphalt to be overlaid.
- Provide a 2 inch wearing course of S-9.5B Superpave asphalt (NCDOT compliant) compacted to 91% on the overlay area. (The total area to be overlaid is approximately 400 Sq.Yds.)
- Stripe/Paint Helo Pad with White Reflective (TT-P-1952, Paint, FED-STD-595, chip No.17875, and TT-B-1325 glass spheres, type III, gradation A.) marking paint to match existing layout exactly.
- Apply paint evenly to the pavement area to be coated at a rate of 2.5 plus or minus 0.10 square meter per liter 105 plus or minus 5 square feet per gallon.
- Clean up and haul off all debris and soil/rock materials to prevent Foreign Object Damage (F.O.D.) to aircraft.

**Special Requirements:**

- Proceed with caution as not to damage any of the landing lights.
- Surrounding buildings will remain in operation during the entire construction period. The contractor shall conduct their operations so as to cause the least possible interference with normal operations of the activity.

**General Requirements:** None Identified

**Submittals:** None Identified

**Special Scheduling and Access:** The Point of Contact at the work site for this project is Inspector Rasenberger at 545-9251. Make arrangements with the POC one week prior to the project start date so that the proper people are notified and work can commence.

**Special Conditions:** None Identified

**Hazardous Materials:** None Identified

**Environmental Requirements:** None Identified

CONTRACT # N40085-09-B-0411  
PROJECT # 9M015CN  
MAXIMO# 4194166

**TITLE: ONSLOW BEACH - PAVE AREA FOR BASKETBALL COURTS**

**ATTACHMENTS:**

1. **Site Plan**
2. **R.E.I.R.**

**SCOPE OF WORK**

**General Description:**

The contractor shall provide all material, labor, equipment and supervision required to accomplish the following: Grade, prep. and pave the area as shown on site plan to be converted into basketball courts. (Approx 1,112 Sq. Yds.). The measurements furnished here are for reference only.

**Detailed Requirements and Specifications:**

**The Contractor Shall:**

- Locate and mark all underground utilities as necessary prior to starting work.
- Spray entire area to be paved with Round-up Pro allowing 10 days for results.
- Remove the wooden fence surrounding the area to be paved. Remove wooden benches, any organic material and any other objects that interfere with grading and paving the area as shown in the site plan.
- Grade and prep existing gravel and rock, Prepare and roll sub-base installing 1 ½" size ABC crushed stone (NC DOT Compliant) up to 235 tons as shown in the site plan, to supplement the existing sub-base and to achieve a total of approximately 4" minimum of compacted base under the new asphalt.
- Provide a 2" wearing course of S-9.5B Superpave asphalt (NC DOT Compliant) compacted to 91% in area shown on site plan.
- Ensure paved area is graded to allow for rain to run off and to prevent standing water.
- Clean up and haul off all debris, soil/rock and materials.

**Special Requirements:**

Surrounding buildings will remain in operation during the entire construction period. The contractor shall conduct their operations so as to cause the least possible interference with normal operations of the activity.

**General Requirements:** None Identified

**Submittals:** None Identified

**Special Scheduling and Access:** Contractor shall contact POC Sam O'Leary at 450-7052 one week prior to starting project so arrangements can be made to have area clear of vehicles.

**Special Conditions:** None Identified

**Hazardous Materials:** None Identified

**Environmental Requirements:** None Identified

CONTRACT # N40085-09-B-0411  
PROJECT # 9M015CN  
MAXIMO# 4194166

**TITLE: BUILDING 1340 BASKETBALL COURT OVERLAY**

**ATTACHMENTS:**

1. Site Plan

### **SCOPE OF WORK**

**General Description:** The contractor shall provide all material, labor, equipment and supervision required to accomplish the following. Provide a 2" asphalt overlay on the Basketball Court on the side of Bldg. 1340. (Approx. 1,060 Sq. Yds.). The measurements furnished here are for reference only.

#### **Detailed Requirements and Specifications:**

##### **The Contractor Shall:**

- Spray area to be paved with Round-up Pro where vegetation exists allowing 10 days for results.
- Remove any sand, rocks, loose asphalt, dirt, and organic material and expose the edges of the asphalt to be overlaid.
- Clean the designated overlay area (by sweeping or some other means) and prep for new asphalt.
- Apply a tack coat at the manufacturer's specifications on the existing asphalt to be overlaid.
- Provide a 2 inch wearing course of S-9.5B Superpave asphalt (NCDOT compliant) compacted to 91% on the overlay area. (The total area to be overlaid is approximately 1,060 SY.)
- All paved areas shall be graded to allow a minimum 2% slope away from the buildings and towards existing drainage.
- Stripe to match existing layout.
- Clean up and haul off all debris and soil/rock materials.

**Special Requirements:** Surrounding buildings will remain in operation during the entire construction period. The contractor shall conduct their operations so as to cause the least possible interference with normal operations of the activity.

**General Requirements:** None Identified

**Submittals:** None Identified

**Special Scheduling and Access:** The Point of Contact at the work site for this project is Dawn Williams at 450-6807 or 382-4830. Make arrangements with the POC one week prior to the project start date so that the proper people are notified and work can commence.

**Special Conditions:** None Identified

**Hazardous Materials:** None Identified

**Environmental Requirements:** None Identified