

**REPLACE AUTOMATIC DOORS TO MEET JOINT COMMISSION
REQUIREMENTS, BUILDING NH 100,
CAMP LEJEUNE, NORTH CAROLINA**

1. **GENERAL INTENTION.** It is the declared and acknowledged intention of this solicitation to obtain the supervision, expertise, labor, materials, equipment to remove the existing automatic doors and install new with positive latching auto doors to meet Joint Commission requirements. Naval Hospital, Camp Lejeune North Carolina.
2. **LOCATION.** The work locations are various and identified on the enclosed drawings, Building NH100, Camp Lejeune NC. located on 100 Brewster Boulevard.
3. **DETAILED REQUIREMENTS.** The Contractor shall:
 - a. Adhere to all specified information within these pages. Shall meet or exceed the manufacturer's specifications and adhere to guidelines as follows:
 - b. Remove the existing 6070 1/34" Doors and Pneumatic operator system in the areas as indicated below by door number.

Doors: C232, C264, C264D, C226, S205A, S215B, S226A, C226A, S242B
 - c. Install new doors a total of 9 pairs of 6070, 1 3/4 inch plastic Chappell laminated wood doors equal to original in structure and fire rating.
 - d. Use Hager 780-22HD 83 inch clear Roton hinges to install doors to frame.
 - e. Install Dorma ED800j x 689 Low E door operators to include Dorma WS/RFT-1 wireless wall switches, Dorma 800RFR, Dorma PT-2 Power Transfer Cable's, Dorma ES9400 x YR23x 630 Electric latch retraction vertical rod exits and Dorma PS501 power supply and any other components as required to provide full function to the door operating system and provide positive latching requirements as mandated by the Joint Commission.

Note: Power will be provided by Naval Hospital Facilities Department to close proximity to door header.
 - f. Install Hager 190S 36 x 34 Armor plates on doors

4. SPECIAL REQUIREMENTS. The Contractor shall:

- a. Commence work under this contract within thirty (30) calendar days after award notification or any other communication authorizing the Contractor to proceed by the Contracting Officer.
- b. Notify the Contracting Office prior to the commencement of work.
- c. Make adjustments to work scheduling and execution as a result of working with an active medical facility and conduct the specific work as described to individual sections of the building as laid out or blocked off by the Officer in Charge. **Contractor shall be prepared and required to conduct work at night or on weekends to facilitate uninterrupted use of facility by the occupants.**
- d. Have all materials on-site prior to commencement.
- e. Prosecute the work diligently.
- f. Complete the work within sixty (60) calendar days.